AEON AIRCONDITIONING SOLUTIONS

Office No 108 & 109. Devashree Garden Commercial Complex. R. W. Sawant Marg. Above Sheetal Dairy. Rutu Park. Thane 400601

HVAC EQUIPMENT QUOTATION / BILL OF QUANTITIES

Customer / Client	ICICI BANK	**Quotation No.**	AAS-10/26-27/005	**Date**	29.10.2028	**Valid Until**	
Project / Site	LOWER PAREL	**Contact Person**	SAMEER SAVANT	**Phone / Email**		**Currency**	INR (₹)

SALE OF HVAC EQUIPMENT

Item	Equipment / Description	Make / Model / Specification	Unit	Qty	Unit Rate	Amount	Notes
A	Daikin Outdoor Units						
1	Supply of Daikin Make 10 HP VRV Outdoor Unit Side Discharge	RXMQ10BRY16	Nos.	1	₹2,24,965.00	₹2,24,965.00	
B	Daikin Indoor Units						
1	Supply of Daikin Make VRV Cassette AC Indoor Unit 2.08 TR	FXFSQ63ARV16	Nos.	2	₹56,680.00	₹1,13,360.00	
2	Supply of Daikin Make VRV Hi Wall AC Indoor Unit 1.08 TR	FXAQ32ARVE6	Nos.	4	₹33,800.00	₹1,35,200.00	
C	IDU Refnut Joints		Nos.	5	₹5,500.00	₹27,500.00	
D	**Supply charges towards Installation of NON VRV HI WALL AC Indoor Unit 1.0 TR**	FTKC35XV	Nos	2	₹36,850.00	₹ 73,700.00	

Equipment subtotal	₹5,74,725.00
GST / tax rate	18%
Tax on equipment	₹1,03,450.50
High Side Total	₹6,78,175.50

INSTALLATION / LABOUR / RELATED SERVICES

Item	Installation / Service Description	Scope / Location / Specification	Unit	Qty	Unit Rate	Amount	Notes
A	Standard Installation Charges for VRV Outdoor Units						
1	Labour charges towards Installation of Daikin Make10 HP VRV Outdoor Unit Side Discharge		Nos.	1	₹ 10,000.00	₹ 10,000.00	
B	Standard Installation, Testing & Commissioning Charges for VRV Indoor Units						
1	Labour charges towards Installation of VRV Cassette AC Indoor Unit 2.08 TR		Nos	2	₹ 3,000.00	₹ 6,000.00	
2	Labour charges towards Installation of VRV Hi Wall AC Indoor Unit 1.08 TR		Nos	4	₹ 1,500.00	₹ 6,000.00	
C	**Labour charges towards Installation of NON VRV HI WALL AC Indoor Unit 1.08 TR**		Nos	2	₹ 1,500.00	₹ 3,000.00	
D	Installtion IDU Refnets (Y-Distribution) Joints for Units		Nos	5	₹ 500.00	₹ 2,500.00	
E	Refrigerant Piping with Rubber Nitrile insulation						
1	Supply & Labour Charges towards Copper Piping with Nitrile Insulation for VRV Units		Rmt	80	₹ 2,450.00	₹ 1,96,000.00	
F	Control Cable :						
1	Supply & Labour towards Communication Cable betweem IDU to ODU 2 Core 1.0 Sqmm with conduits		Rmt	90	₹ 180.00	₹ 16,200.00	
2	Supply & Labour towards Power Cable betweem IDU to ODU 3 Core 1.5 Sqmm		Rmt	15	₹ 210.00	₹ 3,150.00	
G	Drain Pipe :						
1	Supply & Labour charges towards PVC Drain Piping 32mm		Rmt	40	₹ 210.00	₹ 8,400.00	
2	Supply & Labour charges towards PVC Drain Piping 25mm		Rmt	15	₹ 190.00	₹ 2,850.00	
H	Additional Refrigerant Charging as per copper length.		Kg's	10	₹ 1,250.00	₹ 12,500.00	
I	Supply & Labour charges towards Drain Pump for Hi-Wall unit		Nos	4	₹ 7,500.00	₹ 30,000.00	
J	Lifting Shifting VRV ODU & IDU on all floors		Lot	1	₹ 15,000.00	₹ 15,000.00	
K	Transportation of spares and materials		Lot	1	₹ 3,000.00	₹ 3,000.00	
L	Fabrication of Outdoor Unit Stand for 10 HP VRV unit (Table Top)		Nos	1	₹ 9,400.00	₹ 9,400.00	

Installation subtotal	₹3,24,000.00
GST / tax rate	18%
Tax on installation	₹58,320.00
Low Side Total	₹3,82,320.00

Equipment subtotal	₹5,74,725.00
Tax on equipment	₹1,03,450.50
Installation subtotal	₹3,24,000.00
Tax on installation	₹58,320.00
TOTAL INCLUDING TAX	**₹10,60,495.50**

TERMS AND CONDITIONS

1. Taxes	GST / tax is calculated at 18% separately on equipment and installation charges. Confirm applicable tax treatment and registration details before issue.
2. Validity	This quotation is valid until the date shown above. Prices may be revised after expiry or if the specified scope or quantities change.
3. Payment	Payment terms: As agreed
4. Delivery	Delivery / completion schedule: 3 to 4 weeks from receipt of confirmed order, advance and approved technical details, subject to availability and site readiness.
5. Scope	Only items and services listed in the BOQ are included. Any additional materials, civil works, electrical supply, supports, crane / lifting, permissions or out-of-hours work must be agreed and priced separately unless listed above. Mathadi Charges will be in customers scope
6. Site readiness	Customer to provide safe and timely access, clear work areas, power, required permissions and coordination with other trades. Delays caused by site conditions may affect the schedule and cost.
7. Warranty	Manufacturer warranty applies to supplied equipment per the manufacturer's published terms. Warranty excludes misuse, unauthorized repair, poor maintenance and external causes.
8. Changes / cancellation	Changes to quantities, specifications or site conditions require written approval and may change price and schedule. Custom or ordered equipment may not be cancellable or returnable, subject to supplier terms.
9. Acceptance	This quotation is subject to written acceptance / purchase order. Authorized customer signature below confirms acceptance of scope, price and these terms.

For Aeon Airconditioning Solutions		**Customer Acceptance**	
Authorized Signatory	RIZWAN	Name / Title	
Signature / Date	29.10.2026	Signature / Date	
Contact No	9029709319	Contact No	