Supply					
Daikin Air Conditioners					
Sr. No	Model	* Star Rating	Type	Ton	Qty
1	FCVFQ71AV16	3	Inverter Cassette	2.0	1
2	FCVFQ90AV16	3	Inverter Cassette	2.5	1
3	FCVFQ100AV16	3	Inverter Cassette	3.0	1
4	FCVFQ140AV16	3	Inverter Cassette	4.0	11
Mitsubishi Air Conditioners					
Sr. No	Model	* Star Rating	Type	Ton	Qty
1	PLY-SP18EA	4	Inverter Cassette	1.5	2
2	PLY-SP24EA	4	Inverter Cassette	2.0	3
3	PLY-SP30EA	4	Inverter Cassette	2.5	1
4	PLY-SP48EA	5	Inverter Cassette	4.0	3
5	MSY-RJS18VF	3	Inverter Split	1.5	1
LG Air Conditioners					
Sr. No	Model	* Star Rating	Type	Ton	Qty
1	US-Q24ENXE	3	Inverter Split	1.8	1
2	ZTNQ36GNLH1.APUNE	5	Inverter Casette	3.0	1
3	ZTNQ48GMLH2.APUNE	5	Inverter Casette	4	1
4	US-Q19QNXE	3	Inverter Split	1.5	1
5	US-Q19QNXE	3	Inverter Split	1.5	1
6	US-Q19QNXE	3	Inverter Split	1.5	1

Bill of Quantities - Low Side Work					
Sr No	**Description**	**Qty**	**UNITS**	**Rate INR**	**Amount INR**
1	**Standard Installation, Pressure Testing & Commissioning Charges**				
a	Installation of Dx Hi-Wall Units with remote wiring	5	NOS	1,500	7,500
b	Installation of Dx Cassette Units with remote wiring	25	NOS	2,500	62,500
2	**ODU Stands - L Type/Table Top Readymade MS with powder coating.**	30	NOS	800	24,000
3	**Refrigerant piping of copper tubes/piping, with necessary structural, clamps, supports, bends, elbows, reducers, U-bends, oil return & expansion loops, flare nuts / adaptors / any brass fittings, tee connections etc.with insulation.** **Refrigerant Piping (Maxflow / Mandev/ equivalent Pipes) with** **(Superlon/A-Flex/K-Flex/Isoline :Make) piping Insulation)**	800	Rmt	900	720,000
	suitable size as per number of units connected - ODUs to be mounted on Nearest Wall & on Outside on Building Perifery and at nearest location from IDU				
4	**Drain Water Piping P.V.C with nitrile insulation complete with fittings.**				
	suitable size as per number of units connected - 25mm / 32 mm / 40mm	210	Rmt	130	27,300
5	**Control Cabling**				
	Control cabling with saddles / supports to connect outdoor units with respective indoor units.(4 core x 1.5 Sqmm) Make: Polycab/Kei	830	Rmt	140	116,200
6	**Removal of DX Hi-Wall Unit with Copper & Drain pipe**	4	Nos	750	3,000
7	**Removal of DX Cassette Unit with Copper & Drain pipe**	19	Nos	1250	23,750
8	**Removal of DX Mid-Static Ductable Unit with Ducting , Copper & Drain pipe**	2	Nos	2000	4,000
	SUB TOTAL			**RS.**	**988250**
	GST 18%				177885
	Total for Lowside works (Part B)				1166135